# Technical specification

Occupancy		Grids			
Workplace density (NIA per workspace) Means of escape (NIA per person) Core elements (NIA per person) On floor services (NIA per workspace)	8 m <sup>2</sup> 6 m <sup>2</sup> 10 m <sup>2</sup> 8 m <sup>2</sup>	Planning grid Column grid		1.5 m x 1.5 m 6.0 m x 9.0 m	
		Circulation			
Floor plate efficiency NIA:GIA		Percentage of primary circulation to NIA 20%			
Lower ground Ground First	28% 60% 86%	Toilet provision			
Second Third Fourth Fifth	87% 87% 86% 80%	NIA per person Male/female ratio		8 m² (I:8) 60% / 60%	
Sixth	81%	Cycling provision & showers			
Seventh Eighth Ninth Tenth	81% 81% 81% 76%	202 secure cycle spaces 84 folding cycle spaces Shower facilities Male/female ratio Secure lockers	I per 7 staff I per 17 staff I per 60 staff 50% / 50% 0.7 per cycle space		
Plan depth & ceiling height				, ,	,
Window to window Window to core	2l m 10 m – 13 m	Lifts			
Floor to ceiling height	10 111 - 13 111	Retail goods / accessible lift		400d x 2600h 30d x 2200h 30d x 2700h	1,600kg, 21 person 630kg, 8 person 2,000kg, 26 person
Lower ground Ground Office floors (Ist – IOth)	2.625 m – 3.125 m 3.750 m 3.125 m	Car loading Waiting time (up-peak) Handling capacity (up-peak) Waiting time (two way lunchtir Handling capacity (two way lunch time) NIA per person Hall call system: time to destin	unchtime)	80% 25 seconds 12% 35.2 seconds 13% 8 m <sup>2</sup> < 80 seconds	

Raised floors		Comfort		
Typical floors	300 mm (overall)	Airtightness	3 m³/hr/m²	
		Outdoor air	15 l/s	
Church and loadings		Occupancy	8 m²	
Structural loadings		———— Air conditioned space:		
Live:		Summer	24° C +/- 2°C	
Office floors	3.5 kN/m <sup>2</sup>	Winter	21° C +/- 2°C	
Dead:		Mixed mode / natural vent:		
Partitions	1.0 kN/m²	Summer	24° C +/- 2°C	
Loading bay	5.0 kN/m <sup>2</sup>	Winter	21° C +/- 2°C	
Plant room	7.5 kN/m²			
Retail space	4.0 kN/m <sup>2</sup>			
Floors, ceilings & services	0.85 kN/m <sup>2</sup>	Noise criteria		
		External noise intrusion:		
Small power		Open plan	NR38 (Leq)	
		——— Speculative	NR38 (Leq)	
Loading diversified on floor distribution Diversified load (1000 m²)	25W/m² 25W/m²	Cellular offices NR38 (Leq)		
		Sustainability		
Lighting		PREE A. A.		
Day dischating (toward)	2%	BREEAM LEED	Achieved Outstanding Achieved Platinum	
Daylighting (target)	270	EPC	Achieved Rating 'A'	
Average maintained illuminance:		EFC	Achieved Rating A	
VDU use	350-400 lux			
Unified glare rating (UGR)	19	Fibre		
Electrical load allowance	17 12W/m²	TIDIC		
Lighting design load	7W/m <sup>2</sup>	WiredScore	Gold	
219111119 4 2 2 1 9 1 1 2 4 4	,,	SmartScore	Platinum	
		SmartScore	Platinum	

# **Technical specification**

#### **External finishes**

# Façade

- Robust brick piers with precast-concrete scalloped spandrel panels and central mullions in two colour palettes, light and dark brickwork
- Bronze finish curtain walling system with openable windows and bespoke channel detailing

#### Doors

- Glazed capsule doors to main entrance, with bespoke bronze finish channel detailing and curtain walling at high level
- Glazed aluminium door to other ground floor entrances with bespoke bronze finish channel detailing and curtain walling
- Full-height doors on office floorplates with bespoke bronze finish
   Juliette balcony balustrading
- Full-height metal doors to external terraces

# Retail shell & core

# Walls

– Exposed concrete surface, blockwork, and plasterboard walls

# Concrete screed

# Ceiling

Exposed concrete soffit

# Doors

Floors

 Glazed aluminium doors to main entrance, with bespoke bronze finish channel detailing and curtain walling

# Main reception area & café space

# Walls

- External brickwork continues internally, with precast-concrete cladding at high level
- Exposed concrete structural beams
- White-painted acoustic plaster finish at high level and bespoke artwork by Hugo Dalton
- Oak timber cladding to rear wall with concealed doors
- Bronze finish curtain walling

#### Floors

– Warm-tone diamond polish concrete screed with exposed aggregate

# Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

#### Doors

- Glazed capsule doors to main entrance, with bespoke bronze finish channel detailing and curtain walling at high level
- Glazed aluminium door to café entrance with bespoke bronze finish channel detailing and curtain walling

# Reception desk

 Bronze finish expressive metal panels with fin detailing and diamond ground concrete surface

# Office space

# Walls

- Fair-faced concrete to core walls
- Bronze finish curtain walling with metal infill panels

### Floors

- 600 x 600 mm fully accessible raised access floor

# Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

#### Doors

- Full-height office entrance doors with glazed vision panel

#### Blinds

Concealed manual roller blinds

#### Core

# Walls

- Fair-faced concrete to core walls

#### Floors

- Rough-sawn oak board flooring

# Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

#### oors

– Black powder-coated glazed doors, bathroom doors and riser access doors

# Passenger lifts

### Walls

- Black powder-coated expressive metal detailing and wall finish
- Mirror to rear, timber handrail

#### Floors

Oak board flooring

### Ceiling

– Light box with perforated bronze finish metal panel below

# Doors

Black powder-coated metal doors

# Stairs

# Walls

- Fair-faced concrete

#### Floors

Polished concrete screed

### Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits

# Doors

Black powder-coated glazed doors

# Handrail

Oak handrail

# WCs

# Walls

- White ceramic tiles with black metal trim
- Unpainted rough finish plaster to main space
- White painted plasterboard to cubicles

# Floors

- Pattern ceramic tile

# Ceiling

- Exposed concrete soffit to main space
- White painted plasterboard ceiling to cubicles
- Hanging and recessed lights and exposed conduits and ductwork

# Doors

- Grey timber veneer finish doors to cubicles
- Black powder-coated bathroom doors to main space

# **Fixtures**

- White floor standing ceramic WC pans, with black finish exposed wall mounted cistern
- Mahogany toilet seat
- Precast-concrete basins, black PVD coated taps and controls
- Undermounted black metal waste bin
- Black metal frame mirror
- Black PVD toilet roll holders, toilet brush, hooks, stops and ironmongery

## Showers

#### Walls

- White ceramic tiles with black metal trim
- Unpainted rough finish plaster to changing-room space
- Full-height tiling to shower cubicles

# Floors

- Pattern ceramic tile

# Ceiling

- Exposed concrete soffit to changing-room space
- White painted plasterboard ceiling to shower cubicles
- Hanging and recessed lights and exposed conduits and ductwork

# Doors

- Black laminate doors and side panels to cubicles
- Black powder-coated bathroom doors to main space

#### Fixtures

- Black metal and oak benches
- Precast-concrete basins, black PVD coated taps, showers and controls
- Undermounted black metal waste bin
- Black metal frame mirror
- Black PVD hooks, stops and ironmongery

#### **Terraces**

#### Finishes

- Bronze finish bespoke metal balustrading
- Precast-concrete paving slabs

# Lighting

- Linear lighting at low level
- Wall mounted lighting along façade piers